

# **Economic and Social Council**

Distr. GENERAL

ECE/TRANS/WP.5/2006/1/Add.2 30 June 2006

Original: ENGLISH

## ECONOMIC COMMISSION FOR EUROPE

INLAND TRANSPORT COMMITTEE

Working Party on Transport Trends and Economics

Nineteenth session Geneva, 14-15 September 2006 Item 2 (b) of the provisional agenda

# MONITORING OF DEVELOPMENTS RELEVANT FOR THE PAN-EUROPEAN TRANSPORT CORRIDORS AND AREAS

## Infrastructure bottlenecks and missing links

#### Addendum

## Transmitted by the Governments of Croatia and Romania

# **CROATIA**

1. Current capacity problems on inland transport infrastructures (road, rail, inland water)

Inland waterways: Basic bottleneck: Sava (E 80-12) from Yugoslav/Croatian State border to Sisak- upgrading from class III to class Vb is required. Missing link: Danube-Sava Canal (E 80-10) from Vukovar to Samac.

Inland waterways: seasonal.

Inland waterways: Unpredictable restrictions to the use occur due to the water level.

2. Infrastructure measures to alleviate bottlenecks

Inland waterways: dredging and regulatory works on the Sava waterway. Danube-Sava canal, priority I.

GE.06-

| Country | Mode<br>of<br>transport | Route   | Section                  | Traffic<br>loading | Capacity | Extent of action                    |                                       | Operational<br>by |
|---------|-------------------------|---------|--------------------------|--------------------|----------|-------------------------------------|---------------------------------------|-------------------|
|         |                         |         |                          |                    |          | Subject                             | Kind                                  | year              |
| 1       | 2                       | 3       | 4                        | 5                  | 6        | 7                                   | 8                                     | 9                 |
| CR0ATIA | MOTORWAY                | E70     | Border crossing Bregana  | 11,189 (ASDT)      | 40,000   | widening                            | reconstruction                        | 2005              |
|         |                         |         | Border crossing Bajakovo | 6,196 (ASDT)       | 8,000    | widening                            |                                       | 2006              |
|         |                         | E65/E71 | Border crossing Goričan  | 4,872 (ASDT)       | 8,000    | new construction                    |                                       | /                 |
|         |                         | A7      | Border crossing Rupa     | 12,058 (ASDT)      | 10,000   | widening                            |                                       | /                 |
|         |                         | E70     | Zagreb - bypass          | 46,818 (ASDT)      | 50,000   | construction of the third track     |                                       | /                 |
|         |                         | E65/E71 | Toll station Lučko       | 40,323 (ASDT)      | 40,000   | widening                            |                                       | 2006/07           |
|         |                         | E70     | Toll station Ivanja Reka | 27,773 (ASDT)      | 40,000   | widening                            | reconstruction                        | 2005/06           |
|         |                         | E71     | Tunnel Mala Kapela       | 9,664 (ASDT)       | 12,000   | one tunnel tube                     | construction of<br>the second<br>tube | 2009/10           |
|         |                         | E65/E71 | Tunnel Sveti Rok         | 11,363 (ASDT)      | 12,000   | one tunnel tube<br>in traffic       | construction of<br>the second<br>tube |                   |
|         |                         | E65     | Bosiljevo 2 - Rijeka     | 18,000 (ASDT)      |          | upgrading on the full profile 56 km | construction of<br>the second<br>line | 2008              |
|         | STATE<br>ROAD           | SR 1    | Macelj - Zagreb          | 10,442 (AADT)      |          | parallel road                       | construction of the new road          | 2007              |
|         |                         |         | Tušilović - Jošani       | 13,888 (AADT)      |          |                                     |                                       | /                 |
|         |                         |         | Brnaze-Klis-Solin        | 14,414 (AADT)      |          | addition - second line              | designing                             | 2005              |

| Country | Mode<br>of<br>transport | Route   | Section   | Traffic<br>loading | Capacity | Extent of action               |   | Operational<br>by |
|---------|-------------------------|---------|---|--------------------|----------|--------------------------------|---|-------------------|
|         |                         |         |   |                    |          | Subject                        | Kind  | year              |
| 1       | 2                       | 3       | 4   | 5                  | 6        | 7                              | 8   | 9                 |
| CROATIA | STATE ROAD              | SR 2    | Osijek - south bypass   | 17,364 (AADT)      |          | second line                    | location permit                               | 2005              |
|         |                         | SR 3    | Rijeka - bypass   | 21,854 (AADT)      |          | second line                    | designing                                     | 2005              |
|         |                         | SR 7    | section Darda -Osijek   | 10,075 (AADT)      |          | new road                       | designing                                     | 2005              |
|         |                         | SR 8    | section Mučići - Rijeka   | 12,340 (AADT)      |          | parallel road                  | construction of the new road                  | 2005              |
|         |                         |         | Šibenik bypass  | 15,272 (AADT)      |          | parallel road                  | construction of the new road                  | 2005              |
|         |                         |         | Plano-Kaštel Sućurac  | 19,816 (AADT)      |          | second track                   | designing                                     | 2006              |
|         |                         |         | Stobreć-Tučepi  | 11,583 (AADT)      |          | parallel road                  | designing                                     | 2005              |
|         |                         | 1 88 40 | Zagreb - Velika Gorica -<br>Buševec   | 40,980 (AADT)      |          | bypass of the<br>Velika Gorica | designing-<br>construction of<br>the new road | 2005              |
|         |                         | SR 66   | section Ičići - Rijeka  | 14,763 (AADT)      |          | bypass of Opatia riviera       | designing                                     | 2005              |
|         |                         | SR 102  | section Njivice - Krk   | 8,725 (AADT)       |          | research of the alignment      |   | 2006              |
|         |                         | SR 309  | Sv.Nedjelja - Samobor   | 15,133 (AADT)      |          | second line                    | preparing for designing                       | /                 |
|         |                         | SR 510  | Connecting Road –<br>Motorway Zagreb-<br>Goričan with SR 2 from<br>interchange Varaždin | 14,562 (AADT)      |          | second line                    | preparing for designing                       | /                 |

#### 1. <u>Current capacity problems on inland waterway transport infrastructures</u>

Concerning the AGN inland transport waterways, on the Romanian Danube river sector between 863 km (Iron Gates II) -175 km (Braila) there occur navigation bottlenecks due to the variable flow regimen and during the low water periods due to the low depths of 1-1.5 m, much lower than the recommended minimal depths, of 2.5 m. Such phenomena occur in periods of 60 to 150 days/year.

There are not important bottlenecks on major transport axes in the AGC and AGTC lines in Romania, excepting those at the crossing borders.

Regarding the inland transport waterways seasonal summary of LAD's (Least Available Depth) for the Lower Danube has been defined by the Danube Commission at 2.5 m.

In the field of road transport the main problems identified in our country are connected to: congestion on inner city routes; during week-ends, on main national roads like DN1 (E60), between Comarnic and Predeal; temporary, during summer, DN39 Constanta-Mangalia; DN7 Valea Oltului and DN66 Valea Jiului, daily.

In order to avoid the traffic congestion in inner cities, it started the construction of some alternative routes to go around the city (around the capital-Bucharest and other congested cities).

The causes of bottlenecks are: the border crossing traffic, the expanding of the cities, the commercial activities around them, and the increased number of cars on the same infrastructure.

The consequences of those congestion phenomena are the decrease of throughput capacity of infrastructure, and time wasted for ships and cargo, as well as for railway and road transport, and higher costs for fuel.

#### 2. Regulatory measures to alleviate bottlenecks

Romania conducted some studies to underline the differences between the social and economic slow-down in the Eastern part of the country and the linear development in the rest of the country.

In the road sector, a solution offered by Romania was the construction of a 1,065 km long Budapest-Odessa Corridor (Budapesta-Nyiregyhaza-Csengersima/Petea-Baia Mare-Borsa-Suceava-Iasi-Sculeni-Chisinau-Perfomaise/Kucurham-Odesa). Both Hungarian and Romanian Parties had expressed their support for the motorway project. This solution will bring an economical evolution, providing a certain connection between the following countries: Austria-Hungary-Romania-Moldavia-Ukraine.

The motorway Vaja-Baia Mare (approximately 145 km, 65 km in Hungary and 80 km in Romania) establishes a connection between the Northern part of Romania (and in long term the Eastern part, too), and the M3 motorway from Hungary, situated on the Pan-European corridor no.V. This motorway will represent the third high-speed connection between Romania and

Hungary, the first two connections being already planned on the routes Szeged- Nagylak/Nadlac-Arad and the axe Debrecen-Biharkesztes/Bors- Cluj-Napoca.

In the inland transport waterways the following measures will been undertaken:

Feasibility study to improve the conditions for navigation on Calarasi (175 km) – Braila (375 m) sector was done in 2004 – 2005. The works will start in 2006;

Feasibility study to improve the conditions for navigation on Iron Gates II (873 km) – Calarasi (375 km) sector will start in 2006 and the works will start in 2008.

Regarding the railway transport, it is necessary to improve the border crossing procedures and to begin the negotiations of the new border crossing agreements on railway transport.

## 3. Infrastructure measures to alleviate bottlenecks

For Calarasi–Braila sector of the Danube, the following works are needed: bottom sill, guiding wall and banks protection.

With respect to railway transport, it is necessary to plan the construction of a double line on Corridor IV between Curtici and a border with Hungary during the upgrading of line Curtici–Simeria, with a deadline of 2012.

In order to alleviate the bottlenecks in the road infrastructure, a project was developed to:

expand from 2 road lanes to 4 road lanes the national roads, which are going out of big cities, in order to absorb the excess of high traffic volume;

expand the National Road no. 1, from 2 road lanes to 4 road lanes (for a better and faster connection between Henry Coanda International Airport and Bucharest, the capital);

build by-passes in big cities and in sensitive points of the national road network.

At Tecuci, a by-pass was achieved using Phare funds.

Right now, 5 by-passes are under construction and there is also an ongoing project for another 35 by-passes, in different phases of contracting, financing and implementation.